

15.159.21659.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

API NUMBER 15-159-21,659
LEASE NAME Wilkey Livestock Sales
WELL NUMBER 2-23
SPOT LOCATION SW NE SW
SEC. 23 TWP. 21 RGE. 8 (E)OR(W)
COUNTY Rice
DATE WELL COMPLETED 8-11-83
PLUGGING COMMENCED 8-11-83
PLUGGING COMPLETED 8-11-83

LEASE OPERATOR Transierra Exploration Corporation

ADDRESS 1391 Carr #311 Lakewood, CO 80215

PHONE #(316) 792-5020 OPERATORS LICENSE NO. 7042

CHARACTER OF WELL D & A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Merlin Unruh, Halstead, Ks.

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3440

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 270' w/50 sacks 60/40 pozmix, 2% gel 3% cc thru drill pipe

Top Plug: @ 40' w/1/2 sack hulls and 10 sacks cement
10 sacks cement in Rat Hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE No. 5929
ADDRESS P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, SS.

Bill Draney (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Bill Draney

(ADDRESS) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 13 DAY OF August, 1983

Devin M. Waque
NOTARY PUBLIC

MY-COMMISSION EXPIRES: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION FORM CP-4
REVISED 06-83

AUG 16 1983
CONSERVATION DIVISION
Wichita, Kansas
8-16-83

DRILLERS' WELL LOG

DATE COMMENCED: August 5, 1983
DATE COMPLETED: August 11, 1983

Transierra Exploration Corp.
WILKEY LIVESTOCK SALES 2-23
SW NE SW
Sec. 23, T21S, R8W
Rice County, Ks.

0 - 2534' Surface Soil, Sand, Red Bed,
Shale
2534 - 2765' Lime
2765 - 2769' Shale
2769 - 2950' Lime & Shale
2950 - 3274' Lime
3274 - 3394' Shale, Lime, Chert, Sand
3394 - 3440' Shale
3440' RTD

ELEVATION: 1636 K.B.

FORMATION DATA

Topeka 2534'
Hebner 2765'
Toronto 2781'
Br. Lime 2912'
Lansing 2950'
Base K.C. 3274'
Marmaton 3281'
Conglomerate 3322'
Mississippi 3344'
Kinderhook 3394'
RTD 3440'

Surface Pipe: Set new 8-5/8", 20#
pipe @ 206' w/190 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 13 day of August 1983.

My Comm. Expires:

4-29-86

Deborah M. Hogue
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1983

CONSERVATION DIVISION
Wichita, Kansas