


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Rice County, Sec. 14 Twp. 21S Rge. 8W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NE NE NW
Lease Owner Bennett & Gould et al
Lease Name Coyne Well No. 1
Office Address 1212 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 14, 1957 19
Application for plugging filed February 14, 1957 19
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Mississippi Depth to top _____ Bottom _____ Total Depth of Well 3380 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	229.71'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Jetted pits to raise viscosity of mud. Circulated 30 min. Set solid rock bridge at bottom of surface pipe at 229.71.
Filled hole with heavy mud to bottom of surface pipe. Ran 15 sacks of cement through drill pipe. Set top plug at 35' with 5 sacks cement which filled the hole to top of cellar.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
2-23-57

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Cherry Drilling Co., Inc.
Address 102 Insurance Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Franklin Hiebert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Franklin Hiebert
102 Insurance Bldg. (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1957
Maxine Condon Notary Public.

My commission expires Oct. 24, 1960

PLUGGING
FILE SEC 14 T 21 R 8W
BOOK PAGE 142 LINE 24

CHERRY DRILLING CO., INC.

15.159.00295.0000

102 Insurance Bldg.

WICHITA 2, KANSAS

HO 4-5769

ROTARY DRILLING LOG

Lease: Coyne

Company:

Bennett & Gould
1212 Union National Bldg.
and 5806 N. Broadway,
Wichita, Kansas

Well: #1

Location: NE NE NW
Sec. 14-T21S-R8W
Rice County, Kansas

Contractor:

Cherry Drilling Co., Inc.
102 Insurance Building
Wichita, Kansas

Elevation: 1632 Ground
1637 Kelly Bushing

Surface Pipe: 8 5/8" 229.71' overall less
threads, cemented with 275
sacks of 2% cement.

Well Commenced: 2-4-57
Spud 2-4-57, Under Surface 2-5-57

Casing: Dry and Abandoned

Well Completed: 2-14-57

Geologist: Bob Frensley
102 Insurance Building
Wichita 2, Kansas

RECEIVED

0-110 Sand
110-1030 Shale-Shells-Red Bed
1030-1060 Shale
1060-1275 Anhydrite
1275-1425 Lime
1425-1845 Lime and Shale

STATE CORPORATION COMMISSION
NOV 6 1957
CONSERVATION DIVISION
Wichita, Kansas

1845-1925 Lime
1925-2465 Lime and Shale
2465-2620 Lime
2620-2815 Lime and Sand
2815-3280 Lime
3280-3380 Lime and Chert
3380 R.T.D.

GEOLOGIST'S TOPS

HEEBNER 2751
TORONTO 2769
DOUGLAS 2777
BROWN LIME 2897

LANSING 2936
BASE KANSAS CITY 3258
CONGLOMERATE 3324
MISSISSIPPI CHAT 3328

R.T.D. 3380.

The above is a true and correct log to the best of my knowledge.

Subscribed and sworn to before me on this 2nd day of February, 1957.

My commission expires October 24, 1960.

Maxine Condon
Maxine Condon, Notary Public

PLUGGING
FILE SEC 14 T 21 R 8W
BOOK PAGE 142 LINE 24