

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-159-21,720-0000

LEASE NAME Russell Wilkey

WELL NUMBER 1-14

SPOT LOCATION SE SE SE

SEC. 14 TWP. 21 RGE. 8 (E) OR (W)

COUNTY Rice

DATE WELL COMPLETED 11-19-83

PLUGGING COMMENCED 11-19-83

PLUGGING COMPLETED 11-19-83

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Transierra Exploration Corporation

ADDRESS 1391 Carr Street Suite 311 Lakewood, CO 80215

PHONE # (303) 232-0224 OPERATORS LICENSE NO. 7042

CHARACTER OF WELL D & A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? _____
to be filed by _____

Is ACO-1 FILED? operator IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3427'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 300' w/50 sacks cement thru drill pipe
Next Plug: @ 40' w/10 sacks cement " " "
10sacks cement in Rat Hole
10 sacks cement in Mouse Hole
5 sacks cement in water well

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE No. 5929
ADDRESS Box 823 Great Bend, KS 67530

STATE OF kansas COUNTY OF Barton, ss.

Pete Musgrove (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Pete Musgrove
(ADDRESS) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23 DAY OF November, 1983

Dorothy M. Haque
NOTARY PUBLIC

MY COMMISSION EXPIRES: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1983

WICHITA DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

DRILLER'S WELL LOG

DATE COMMENCED: November 13, 1983
 DATE COMPLETED: November 19, 1983

TranSierra Exploration Corp.
 RUSSELL WILKEY 1-14
 SE SE SE
 Sec. 14, T21S, R3W
 Rice County, Ks.

0 - 2757' Surface Soil, Lime, Shale
 2757 - 2761' Shale
 2761 - 2773' Lime & Shale
 2773 - 2780' Lime
 2780 - 2906' Shale
 2906 - 2950' Lime & Shale
 2950 - 3270' Lime
 3270 - 3396' Chert & Lime
 3396 - 3427' Shale
 3427' RTD

ELEVATION:

FORMATION DATA


Heebner	2757'
Toronto	2773'
Douglas	2780'
Br. Lime	2906'
Lansing K.C.	2950'
Base K.C.	3270'
Mississippi	3360'
Kinderhook	3396'
RTD	3427'

Surface Pipe: Set new 8-5/8"
 20# pipe @219' w/150 sacks
 60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss


Pete Musgrove of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



Subscribed and sworn to before me this 23 day of November 1983.

My Comm. Expires:

4-29-86



Notary Public