

State of Kansas



15-009-20865-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

December 8, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1974

CONSERVATION DIVISION
Wichita, Kansas

12-19-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Elmer Zimmerman of Woodman-Tannitti Drlg. Co has this
date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: Vincent Oil Corporation

Complete Address: 719 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Lamatsch Well No. 1

Location: 175' So. of SE NW SW Sec. 26 Twp. 16 Rge. 12(E)(W) X


County: Barton Total Depth 3380' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks
cement through drill pipe at 500'. Pump 25 sacks cement
through drill pipe at 210'. Push plug and $\frac{1}{2}$ sack hulls to
40' and cap hole with 10 sacks cement. Bridge rathole and
cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent