

State of Kansas



15.185.20090.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 8, 1968.

Dear Sir:

Mr. Jack Flake of Woodman & Iannitti has this
date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman & Iannitti

Complete Address: 706 Union National Bldg., Wichita, Kansas 67202

Lease Name: Pundsack Well No. # 1

Location: C W/2 NW SE Sec. 12 Twp. 21 Rge. 14 (E)(W) W

County Stafford Total Depth 3710' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

270' of 8 5/8" surface pipe, cement circulated with 135 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sacks of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1968

CONSERVATION DIVISION
Wichita, Kansas

Arlene Elving
Conservation Division Agent