



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 14 1971

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Reserve Pipeline has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Reserve Pipeline Inc.

Complete Address: 1116 N. Washington, Liberal, Kansas

Lease Name: Crist Well No. 1

Location: C SE Sec. 13 Twp. 21 Rge. 34 (E) (W)

County: Finney Total Depth 2605' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 371' circulated w/ cement. 4 1/2" to 2605' cemented.


Top perforations 2560' Plug bottom w/ sand & 5 sacks cement.

Top of cement 1875'. Mud 1875' to 370'

Spot 35 sacks cement 370' to 270' Mud 270' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent