

State of Kansas



15.159.20034.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAY 1 1967

April 26, 1967 CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

5-1-67

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this
date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis

Complete Address: 909 Palace Bldg., Tulsa, Oklahoma

Lease Name: Moore "F" Well No. 1

Location: NW NW NW Sec. 17 Twp. 21 Rge. 8 (E) (W) X


County Rice Total Depth 3452' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

Fill hole with mud to 230'. Push plug and 1/4 sack hulls to 230' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent