

15.185.01861.0000

Form CP-3
Rev. 6-26-62

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

7-28-66

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name National Cooperative Refinery Assoc.

Complete Address: P. O. Box 6, Great Bend, Kansas

Lease Name Frey "A" Well No. # 2

Location NE SW NE Sec. 7 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3728'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Gomstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 10:15 AM Day 25th Month July Year 1966

The Above well was plugged as follows:

. 890' of 8 5/8" surface pipe, cement circulated. 3716' of 5 1/2" long string,
cement unknown. This is an open hole. Tubing was ate up, and had parted
at 500'. 500' of tubing was recovered from the hole. 5 1/2" bridge plug
was pushed to top of tubing at 500', sand and rock bridge from 500' to
490', and cemented with 5 sacks, through the dump bailer. 437' of 5 1/2"
long string was recovered from the hole. Hole was bailed down to 300',
rock bridge from 300' to 290', and cemented with 4 yards of ready-mix
cement, from 290' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/28/66
INV. NO. 3644-W