

62

KANSAS
STATE CORPORATION COMMISSION

15.185.20090.0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed February 8, 1968.

Operator's Full Name Woodman & Iannitti

Complete Address: 706 Union National Bldg., Wichita, Kansas 67202

Lease Name Pundsack Well No. # 1

Location C W/2 NW SE Sec. 12 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Woodman & Iannitti

Address: 706 Union National Bldg., Wichita, Ks. 67202 License No. _____

Operation Completed: Hour 6:00PM Day 14th Month February Year 1968

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated with 135 sacks. Hole was
filled with drilling mud. 25 sacks of cement was spotted at 480', through
the drill pipe, with cement from 480' to 405'. 25 sacks of cement was
spotted at 240', through the drill pipe, with cement from 240' to 165'.
Fluid was now at 38' in the hole. Cementing plug bridged with 1 sack of
dry cement and 1/2 sack of hulls on fluid at 38', and cemented with 9 sacks,
with cement from 30' to the base of the cellar. Rat hole bridged and cemen-
ed with 2 sacks. Cement was pumped with 8% Gel-Mud, by Sun Cementing Company.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

FEB 15 1968

CONSERVATION DIVISION
Wichita, Kansas

DATE 2-15-68

INV. NO. 7274-W