

15.185.30001.0000 R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 8 1965

CONSERVATION DIVISION
Wichita, Kansas

1-8-65

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Blakeslee Well No. # 1

Location C NE SW SW Sec. 12 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth ~~4690~~ 3690

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson Oil Company

Address: 1425 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 8:45PM Day 2nd Month Jan. Year 1965

The Above well was plugged as follows:

367' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid
was up in the hole. 1st cementing plug and 1/4 sack of hulls was pushed
in fluid to 300', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
with hulls on fluid at 40', and cemented with 10 sacks to the base of
the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INDEXED

DATE 1-8-65

INV. NO. 497-W