

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Reserve Pipeling, Inc.

Complete Address 1116 N. Washington, Liberal, Kansas 67901

Lease Name Crist Well No. 1

Location C SE Sec. 13 Twp. 21 Rge. 34 ~~(E)~~ (W)

County Finney Total Depth 2605'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 11 Month 5 Year 1971

The above well was plugged as follows:

8 5/8" to 371' circulated w/ cement. 4 1/2" to 2605' cemented.

Top Perforations 2560' Plug bottom w/ sand & 5 sacks cement.

Top of cement. 1875' Mud 1875' to 370'

Spotted 35 sacks cement 370' to 270' Mud 270' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 1515' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: Edward A. Eves
Well Plugging Supervisor

DATE 5/14/71

INV. NO. 3700-W