

15.159.00548.0000



KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H.L. Herbel

Complete Address: Box 327 Chase, Kansas 67524

Lease Name Dilley R.A. Well No. # 1

Location G SW SW Sec. 23 Twp. 21 Rge. 8 (W) (W)

County Rice Total Depth 3442'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Pipe Pullers, Inc.

Address: Ellinwood, Kansas License No. 462

Operation Completed: Hour 730 P^m Day 22 Month 8 Year 68

The Above well was plugged as follows:

8 5/8"-263'-Circulated w/cement. 5 1/2"-3435'-Cemented. Top Perf. 3353'.

Sand hole to 3340'. 5 Sax. cement 3340' to 3300'. Mud 3300' to 250'.

Bridge 250' to 240'. 25 Sax. cement 240' to 165'. Mud 165' to 40'.

Bridge 40' to 30'. 10 Sax. cement 30' to 0. Pulled 2805'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/26/68
INV. NO. 8344-W

Signed: [Signature]
Well Plugging Supervisor