

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 9/29/56

LEASE NAME BAUER

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

330 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR CHAPMAN EXPLORATION, INC.

SEC. 32 TWP. 21S RGE. 14 (X) or (W)

ADDRESS 6100 S. YALE, SUITE 1816, TULSA, OK. 74136

COUNTY STAFFORD

PHONE#(918) 496-7882 OPERATORS LICENSE NO. 6939

Date Well Completed 9/29/56

Character of Well Was oil well, now plugged

Plugging Commenced 7/10/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/17/89

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City & Great Bend

Is ACO-1 filed? No If not, is well log attached? None Available

Producing Formation Arbuckle Depth to Top 3842 Bottom 3860 T.D. 3860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & water	3842	3860	5 1/2	3842	none
Lansing-KC	water	3446	3678	8 5/8	280	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Dumped 14 sacks frac sand down 5 1/2". RUPU. Dumped 5 sacks cement on top of sand with glass bottom bailer. Run 45 jts. tbq. to 1395' & pumped 385 sacks cement (Halliburton). Had circ. while pumping. Laid down 23 jts. circulate 50 more sacks cement. Pumped 165 sacks between 8 5/8" & 5 1/2". Pull tbq. Wait 6 days. Run wireline. Cement 225' from surface. Cut 8 5/8"  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Virgil L. Johnson employee of Chapman Exp, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Virgil Johnson  
RECEIVED  
STATE CORPORATION COMMISSION  
Virgil L. Johnson  
6100 S. Yale, Suite 1816  
Tulsa, Okla. 74136

SUBSCRIBED AND SWORN TO before me this 28 day of July, 19 89

Julie L. Smith  
Notary Public

My Commission Expires: My Commission Expires October 19, 1991

and 5 1/2" off 4' below ground. Dump two yards concrete down 5 1/2" and 8 5/8".  
Hole full. Job complete.