

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record

K.A.R. 82-2

RECEIVED

SEP 10 2003

KCC WICHITA

API NUMBER 15-18523184-0000
LEASE NAME Spece
WELL NUMBER No. 1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2310 Ft. from South Line of Section
1650 Ft. from West Line of Section

LEASE OPERATOR L. D Drilling SPOT LOCATION 60' S & 60' W of C N/2 S/2 SW
ADDRESS RR #1, Box 183-B Section 32 Township 21s Range 14w
CITY, STATE, ZIP Great Bend, Kansas 67530-0183 County Stafford
PHONE # 620-793-3051 Date Well Completed 09/04/03
Character of Well Dry and Abandoned Date Plugging Commenced 09/04/03
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 09/04/03

The plugging proposal was approved on September 4, 2003 (date)
by Richard Lacey (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3871

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	280			
Redbeds	Shale	280	394	8-5/8"	394'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Received plugging orders 09/03/03 (Steve Middleton). Plugged with heavy mud in hole and between all plugs using 150 sx 60/40 Poz, 6% Gel. Bottom plug @ 3841'-40sx, 2nd plug @ 930'-50sx, 3rd plug @ 420'-50sx and top plug @ 40'-10sx cemented to surface. Plugged Rathole with 15 sx. Plug down at 4:45 pm 09/04/03 by Allied Cementing. Ticket #12756. Reported to KCC 09/04/03 (Richard Lacey).

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D Drilling (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 9th day of Sept. 10 2003

Pamela S. Fields
(Notary Public)



My Commission Expires:

RECEIVED
SEP 10 2003
KCC WICHITA

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Spece No. 1

LOCATION: 60' S & 60' W of C N/2 S/2 SW Section 32 T 21s R 14w
API: 15-18523184-0000 Stafford County, Kansas

OWNER: L. D Drilling
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 28-Aug-03
COMPLETED: 04-Sep-03

TOTAL DEPTH: DRILLER 3871 FEET
LOGGER 3871 FEET

Ground Elevation: 1951
KB Elevation: 1960

LOG

0 -	3 FEET	Top Soil
3 -	40 FEET	Clay
40 -	75 FEET	Sand and Gravel
75 -	240 FEET	Shale and Clay
240 -	891 FEET	Redbeds
891 -	917 FEET	Anhydrite (Driller)
917 -	879 FEET	Shales and Salt
879 -	1875 FEET	Limestone, Shale and Dolomite
1875 -	3871 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Drilled 12-1/4" hole to 394'. Ran 9 joints of new 8-5/8" surface casing. Tally 398', set @ 394' KB.
Cemented with 275 sx 60/40 Poz, 2% Gel & 3% C.C. Plug down at 8:45 pm 08/28/03.
Swift Services, Inc. ticket #5796. Strapped bottom 3 joints, welded collars on top 5 joints.

Plugging Data:

Received plugging orders 09/03/03 (Steve Middleton). Plugged with heavy mud in hole and between all plugs using 150 sx 60/40 Poz, 6% Gel. Bottom plug @ 3841'-40sx, 2nd plug @ 930'-50sx, 3rd plug @ 420'-50sx and top plug @ 40'-10sx cemented to surface. Plugged Rathole with 15 sx. Plug down at 4:45 pm 09/04/03 by Allied Cementing. Ticket #12756. Reported to KCC 09/04/03 (Richard Lacey).

DEVIATION SURVEYS

1/2	degree(s) at	394	feet
1 1/4	degree(s) at	1945	feet
1	degree(s) at	3808	feet