


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 32 Twp. 21S Rge. 14 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NW
Lease Owner Petroleum, Inc.
Lease Name Bauer Well No. 1
Office Address 100 Derby Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 5, 1952
Application for plugging filed May 5, 1952
Application for plugging approved May 5, 1952
Plugging commenced May 5, 1952
Plugging completed May 5, 1952
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 385 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 270' and set first wooden plug at 270'. Cemented and displaced 20 sacks cement through drill pipe on top of plug at 270'. Mudded up to 35' and placed second wooden plug at 35'. Filled hole with 25 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1952

5-9-52

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher

100 Derby Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 1952.

Shulata Friedman
Notary Public.

My commission expires October 13, 1954

PLUGGING
FILE SEC 32 T 21 R 14
BOOK PAGE 14 LINE 14

DRILLER'S LOG BAUER #1

Petroleum, Inc., Lease Owner

Section 32, Twp. 21S, Rge. 14W

Garvey Drilling Company, Contractor

Location: SW SE NW

Drilling Commenced: April 25, 1952

County: Stafford County, Kansas

Drilling Completed: May 5, 1952

Production: D & A

Casing Record: 8 5/8" C 274' w/200 sax

R.T.D.: 3851'

Figures below indicate bottom of formation:

320 Shale & Shells
 425 Sand
 887 Red Bed
 920 Anhydrite
 1660 Shale & Shells
 2090 Lime & Shale
 2200 Lime
 3120 Lime & Shale
 3353 Lime
 3455 Lime & Shale
 3665 Lime
 3807 Lime & Shale
 3822 Shale
 3851 Lime

 3851' R.T.D.

Tops:

Heebner: 3316 (-1360)
 Brown Lime: 3434 (-1478)
 Lansing: 3439 (-1483)
 Conglomerate: 3714 (-1758)
 Viola: 3716 (-1760)
 Simpson: 3764 (-1808)
 Arbuckle: 3821 (-1865)

DST #1, 3561-73, open 1 hour, recovered 50' mud, 850# BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fisher
W. W. Fisher

STATE OF KANSAS :
 : SS:
 COUNTY OF SEDGWICK :

Subscribed to and sworn to before me, a Notary Public in said County and State, this 7th day of May, 1952.

PLUGGING
 FILE SEC 32 T 21 R 14
 BOOK PAGE 14 LINE 17

RECEIVED

STATE CORPORATION COMMISSION

MAY - 9 1952

Charlotte Anderson
Notary Public

My commission expires: October 13, 1954 CONSERVATION DIVISION
Wichita, Kansas