


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 32 Twp. 21 Rge. 14 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Isern Brothers etal  
Lease Name Scheufler Well No. 1  
Office Address Box 45, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 25, 1956 19  
Application for plugging filed October 25, 1956 19  
Application for plugging approved October 25, 1956 19  
Plugging commenced October 25, 1956 19  
Plugging completed October 25, 1956 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3944 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	<u>Surface Pipe</u>	<u>0</u>	<u>286'</u>	<u>8-5/8"</u>	<u>286'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped mud into hole - pumped 100 sacks bulk cement with 200# Calcium Chloride into hole at 250# P.S.I. by Globe Oilwell Cementing Co.

10-31-56

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Isern Drilling Company  
Address Box 45, Ellinwood, Kansas


STATE OF KANSAS, COUNTY OF BARTON  
I. M. M. Shropshire (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. M. M. Shropshire  
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 56

My commission expires Feb. 10, 1959.

George A. Meyer  
Notary Public.



WELL LOG

ISERN BROTHERS ETAL, OWNER - SCHEUFLER #1  
SE/4 SE/4 SW/4 Section 32, Township 21, Range 14W,  
Stafford County, Kansas

ELEVATION: 1948 Gr

Figures indicate bottom of formation:

0	to	255	sand & clay
		286	shale
		330	red rock
		420	sand
		875	red rock
		890	Anhydrite
		935	sand
		1680	shale & shells
		2010	lime & shale
		3130	shale & shells
		3400	lime & shale
		3471	lime
		3795	lime & shale
		3875	lime, shale & chert
		3880	chert & shale
		3944	shale & lime
		3944	Rotary Total Depth
			D&A

PIPE RECORD:

8-5/8" set at 286'  
Cemented with 225 sacks cement  
and 500# Calcium Chloride  
October 17, 1956

Rotary Commenced 10-17-56  
Completed 10-25-56

STATE OF KANSAS )  
COUNTY OF BARTON ) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 26th day of October, 1956.

George A. Meyer  
Notary Public

My commission expires Feb. 10, 1959.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1956

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 32 T. 21 R. 14W  
BOOK PAGE 110 LINE 41