

15.185.00594.0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
210 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12/2/56

LEASE NAME BAUER

WELL NUMBER 4

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 21S RGE. 24 (R) or (W)

COUNTY Tulsa

Date Well Completed 12/8/56

Plugging Commenced 7/11/89

Plugging Completed 7/17/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CHAPMAN EXPLORATION, INC.

ADDRESS 6100 S. Yale, Suite 1816, Tulsa, Okla. 74136

PHONE#(918) 496-7882 OPERATORS LICENSE NO. 6939

Character of Well was oil well, now plugged
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City & Great Bend

Is ACO-1 filed? no If not, is well log attached? none available

Producing Formation Lansing-KC Depth to Top 3557 Bottom 3567 T.D. 3906

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|------------|-------------|------|------|--------|--------|------------|
| Lansing-KC | Oil & water | 3557 | 3567 | 8 5/8" | 260 | none |
| Arbuckle | Water | 3848 | 3887 | 5 1/2" | 3904 | none |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Halliburton pumped 150 lbs. hulls down 5 1/2" followed by 50 sack cement then 15 sacks gel then 50 lbs hulls then 115 sacks cement. Pumped 120 sacks cement between 5 1/2" & 8 5/8" Wait 6 days. Ran wire line. Cement 235' from surface. Cut off 5 1/2" & 8 5/8" Dumped 2 1/2 yds. concrete ready mix down 5 1/2" & 8 5/8". Hole full
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Great Bend, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Virgil L. Johnson employee of Chapman Exp., Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Virgil L. Johnson
Virgil L. Johnson
6100 S. Yale, Suite 1816
Tulsa, Okla. 74136

RECEIVED
STATE CORPORATION COMMISSION
7-31-89

SUBSCRIBED AND SWORN Jul 31 1989 before me this 28 day of July, 19 89

CONSERVATION DIVISION
Wichita, Kansas
Julie L. Smith
Notary Public

My Commission Expires: _____ My Commission Expires October 19, 1991