

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

Barton County. Sec. 27 Twp. 16 Rge. 12 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Se, SE, NW
Lease Owner. Francis Oil & Gas, Inc.
Lease Name. John R. Rieman Well No. 1
Office Address. 905 Palace Bldg. - Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed. 8-3-45 19
Application for plugging filed. 1-15-52 19
Application for plugging approved. 19
Plugging commenced. 2-1-52 19
Plugging completed. 2-7-52 19
Reason for abandonment of well or producing formation. - ceased making oil.
If a producing well is abandoned, date of last production. November 1951
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Charles Stough
Producing formation. Arbuckle Depth to top. 3353 Bottom. 3364 Total Depth of Well. 3364 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	water & oil	3353	3364	8-5/8"	300'	None
				5 1/2"	3355	2823

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand to 3540' - dumped 5 sacks cement. Shot pipe off at 2823', pulled pipe and mudded hole to 225' - set rock bridge and 15 sacks of cement. Mudded hole to 35'. Set bridge and 10 sacks of cement at surface.

STATE OF KANSAS
FEB 14 1952
CONSERVATION DIVISION
Wichita, Kansas

2-14-52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Francis Oil & Gas, Inc.
Address. 905 Palace Bldg.
Tulsa 3, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Louis P. Myers (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Louis P. Myers Vice President

905 Palace Building
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of February, 1952

My commission expires 9/15/53

Notary Public.



15-009-01332-00-00

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, KansasCompany - C.E. ASH ET AL
Farm - John R. Riemann "A" No.

1.

SEC. 27 T. 16 R. 12 W
SEc NWDISCOVERY WELL

Total Depth. 3364

Comm. 7-6-45


Comp. 8-3-45

County. Barton
KANSAS

Shot or Treated.

Contractor. C.E. Ash

Issued. 12-1-45

CASING:

8 5/8"

300'

5 1/2"

3355'

Elevation. _____

Production. Pot. 360 B.

Figures Indicate Bottom of Formations.

shells & shale	0-450
sand	510
red bed	785
anhydrite lime	815
shale & shells	1240
salt	1485
lime & shale	1860
lime	1960
lime & shale	2030
lime	2155
shale & shells	2560
lime	2640
shale	2735
lime	2805
shale & lime	2865
lime	2900
shale & shells	2965
lime	3013
shale & shells	3035
shale	3077
lime	3364
Total Depth	

Tops:

K.C. or White Lime	3090
Conglomerate	3352
Arbuckle	3353

JAN 25 1946

PLUGGING

FILE SEC 27 T. 16 R. 12 W

BOOK PAGE 139 LINE 29