


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 27 Twp. 16 Rge. 12 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE

Lease Owner C. O. Chubb and Duke Drilling Company

Lease Name Penka Well No. 2

Office Address P. O. Box 123, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 25, 1958

Application for plugging filed October 25 1958

Application for plugging approved November 6 1958

Plugging commenced October 25 1958

Plugging completed October 25 1958

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation Arbuckle - Was dry Depth to top 3384 Bottom _____ Total Depth of Well 3395 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	330	8 5/8"	330	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud to 310'. Set bottom plug at 310' with 1/3 sack hulls and 25 sacks cement. Filled hole with heavy mud to 40'. Set top plug at 40' with 1/3 sack hulls and 10 sacks cement.

11-8-58

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company

Address P. O. Box 123, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Clair E. Stimson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clair E. Stimson

P. O. Box 123, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 1958

My commission expires July 29, 1961

Notary Public.

PLUGGING
FILE SEC. 27 T 16 R12W
BOOK PAGE 143 LINE 6

WELL LOG

Date Started: October 14, 1958
Date Completed: October 25, 1958

Penks #2
SE NE NE
Section 27-16-12
Barton County, Kansas

Elevation	1923'	K.B.
Anhydrite	803'	1120
Heebner	2993'	-1070
Toronto	3010'	-1087
Douglas	3021'	-1098
Iatan	3082'	-1159
Lansing	3098'	-1175
Conglomerate	3370'	-1447
Arbuckle	3384'	-1461
R.T.D.	3395'	-1472

0' - 40'	Surface Clay
40' - 75'	Shale and Clay
75' - 100'	Shale
100' - 110'	Sand
110' - 120'	Shale
120' - 135'	Sand
135' - 155'	Shale
155' - 185'	Blue Shale
185' - 245'	Clay and Shale
245' - 265'	Sand
265' - 330'	Shale and Clay
330' - 590'	Blue Shale
590' - 803'	Red Bed
803' - 832'	Anhydrite
832' - 1160'	Shale and Shell
1160' - 1235'	Shale
1235' - 1384'	Shale and Shell
1385' - 1476'	Salt and Shale
1476' - 1500'	Shale and Shell
1500' - 1600'	Shale with Lime Streak
1600' - 1800'	Lime and Shale
1800' - 2105'	Lime and Shale
2105' - 2480'	Lime and Shale
2480' - 2680'	Lime and Shale
2680' - 2770'	Lime
2770' - 2924'	Lime
2924' - 2993'	Lime
2993' - 3021'	Heebner
3021' - 3098'	Lime
3098' - 3135'	Lansing
3135' - 3255'	Lime
3255' - 3370'	Lime
3370' - 3384'	Conglomerate
3384' - 3395'	Arbuckle
3395'	R.T.D.

REC
STATE CORPORATION

NOV 8 1958

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton

I, Clair E. Stinson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: Clair E. Stinson

Subscribed and sworn before me this 7th day of November, 1958.

James L. Lacy
NOTARY PUBLIC

My commission expires: July 29, 1961

PLUGGING
FILE SEC. 27 T. 16 P. 120
BOOK PAGE 143 LINE 6