

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-009-23,232-00-00

LEASE NAME Hitschman

WELL NUMBER 6-A

SPOT LOCATION SE SE SW

SEC. 27 TWP. 16 RGE. 12 (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED 8-23-83

PLUGGING COMMENCED 8-23-83

PLUGGING COMPLETED 8-23-83

LEASE OPERATOR Reif Oil Operations, Inc.

ADDRESS P.O. Box 298 Hoisington, KS 67544

PHONE # (316) 653-7745 OPERATORS LICENSE NO. 5770

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Gilbert Scheck
to be filed by

IS ACO-1 FILED? operator IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3387

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Bottom Plug: @ 3350' w/20 sacks 50/50 pozmix 4% gel 3% cc thru drill pipe

Next Plug: @ 780' w/90 sacks

Next plug: @ 400' w/40 sacks

Top Plug: @ 40' w. 1/2 sacks hulls for solid bridge & 10 sacks cement
10 sacks cement in Rat Hole

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Duke Drilling Co., Inc. LICENSE NO. 5929
ADDRESS P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.

(SIGNATURE) Bill Draney

(ADDRESS) P.O. Box 823 Great Bend, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29 DAY OF August, 1983

Heidi M. Hogue
NOTARY PUBLIC

MY COMMISSION EXPIRES: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION
FORM CP-4
REVISED 06-83

SEP 1 1983 9-1-83

CONSERVATION DIVISION
Wichita, Kansas

15-009-23232-00-00

DRILLERS' WELL LOG

DATE COMMENCED: August 17, 1983
DATE COMPLETED: August 23, 1983

Reif Oil Operations, Inc.
HITSCHMAN 6-A
SE SE SW
Sec. 27, T16S, R12W
Barton County, Ks.

ELEVATION: 1912 K.B.

0 - 786' Surface Soil, Post Rock, Shale
786 - 811' Anhydrite
811 - 2696' Lime & Shale
2696 - 2979' Lime
2979 - 2983' Shale
2983 - 2995' Lime & Shale
2995 - 3008' Lime
3008 - 3069' Shale
3069 - 3083' Lime & Shale
3083 - 3334' Lime
3334 - 3362' Shale, lime, Chert, Sand
3362 - 3387' Dolomite
3387' RTD

FORMATION DATA

Anhydrite	786'
Topeka	2696'
Heebner	2979'
Toronto	2995'
Douglas	3008'
Br. Lime	3069'
Lansing K.C.	3083'
Base K.C.	3334'
Conglomerate	3350'
Arbuckle	3362'
RTD	3387'

SURFACE PIPE: Set new 8-5/8"
24" pipe @ 353' w/175 sacks
60/40 pozmix, 2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 29 day of August 1983.

My Comm. Expires:

4-29-86

Harold M. Hague

Notary Public

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1983

CONSERVATION DIVISION
Wichita, Kansas