



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Dare has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Dare Gas Inc.

Complete Address: Box 544, Liberal, Kansas

Lease Name: Howell Well No. 1

Location: C NW SE Sec. 19 Twp. 21 Rge. 42 (E) (W)

County: Hamilton Total Depth 2850' Oil Well

Gas Well ☒ Input Well ☐ SWD Well ☐ D & A ☐ Lost Hole ☐

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 200' circulated w/ cement. 4 1/2" to 2850' cemented.

Top perforations 2732' Plug bottom w/ 15 sacks cement

Top of cement 2610' Mud 2610' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 200'

Spotted 35 sacks cement 200' to 100' Mud 100' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Edgar J. Eves
Conservation Division Agent