



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

March 19, 1972

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent) **RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 23 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

3-23-72

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: H. C. Bennett & C. E. Gould

Complete Address: 1212 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name: Hughes Well No. 1-A

Location: C NW SE Sec. 6 Twp. 21 Rge. 7  (E)  (W)  X

County: Rice Total Depth 3380' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 225'. Push plug and 1/4 sack hulls to 225' and

cement hole with 25 sacks cement through drill pipe. Fill hole with

mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10

sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent