

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-185-12190-0001

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 8 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Buck Unruh of Southwest Casing Pulling has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name: Fanshier "E" Well No. # 1

Location: NE SW NE Sec. 9 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3685 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

125' of 8 5/8" surface pipe, cement circulated. 3679' of  
5 1/2" long string, cemented with 100 sacks. Top perforation  
3545'. Sand to 3530', cement with 5 sacks.

Due to water conditions and the short length of surface  
pipe a squeeze job will be necessary.

Very truly yours,

Archie Elving  
Conservation Division Agent