

State of Kansas



15-009-03376-00-00

FORM - CP-2
Rev. 9-8-64

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Specter Pipe & Supply has this
date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas

Lease Name: Paul Dolechek Well No. # 9

Location: SW NE SE Sec. 24 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3362 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

8 5/8" 276' Cwc.

Set bottom plug @ 3140' & dumped 5 sax cement with dump bailer. Pulled
pipe. Mudded hole to 270'; set rock bridge; displaced 25 sax cement.
Mud to 40'; set rock bridge & dumped 10 sax cement, cementing to
base of cellar.

Very truly yours,

Don L. Luman
Conservation Division Agent