

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1965

CONSERVATION DIVISION
WICHITA, KANSAS
3-31-65

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name J. H. Fanshier Well No. # 2

Location NW SW NW Sec. 9 Twp. 21 Rge. 13 (E) (W)W

County Stafford Total Depth 3592'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:30AM Day 29th Month March Year 1965

The Above well was plugged as follows:

210' of 8 5/8" surface pipe, cemented with 190 sacks. 3582' of 4 1/2" long
string, cemented with 100 sacks. Top perferation 3536'. Bottom of the
hole was sanded to 3500', and cemented with 3 sacks. 3091' of 4 1/2" long
string was recovered from the hole. Fluid level was up in the hole.
Bridge plug was pushed in fluid to 210', and 10' of rock bridge on plug.
5 sacks of cement was mixed in barrel, and put on plug at 200', through
the dump bailer, and let set over-night. Next morning hole was bailed
dry, and 20 sacks of cement was added to the plug. Hole was filled with
mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/31/65

INV. NO. 911-W

15.185-11994.0000

The Well Plugging Authority
of March 17, 1965, gave this
well in Barton County. This
is in error. It should have
been Stafford County

Archie Elving

Archie Elving

STATE COMMISSION
MAR 31 1965

COMMISSION AND ENGINEER
WASHTON, KANSAS