

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 15-37  
LOCATION SW-SW-SE  
SEC. 9 TWP. 21 RGE. 13W.

Dry Hole DA Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Fanshier

Operator The Texas Co. Address Box 1801 Wichita Kansas

Field \_\_\_\_\_ County Stafford

Total Depth 3,730 Feet.

Plugging Contractor R+S Pipe Pulling Co

Plugging Contractor's License No. 1

Address Box 192 Ellinwood Kansas

(Describe Briefly the manner in which the well was plugged)

*Surf Pipe 10 3/4 @ 760 feet P. & C.  
7 in @ 3,684 surf. 75' sur. g. cement.  
P.B. to 3,497 - Top Perf. @ 3,462  
Sand to 3,450 and 6 sur. g. cement.  
Pull pipe fill hole with heavy mud and  
r.t. to 240 feet and 25' sur. g. cement and  
heavy mud + r.t. to 50 feet and 10 sur. g. cement  
to base of cellar*

*R.M. Burdette*  
District Conservation Agent

Date June 2 - 1957

PLUGGING  
FILE SEC. 9 T. 21 R. 13W  
BOOK PAGE 15 LINE 37

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 X 1957  
CONSERVATION DIVISION  
Wichita, Kansas