

JP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-01126-0000

Complete Address: 915 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Boyd Well No. 6

Location NE NE NW Sec. 3 Twp. 23 Rge. 17 (E) XX (W) XX

County Pawnee Total Depth 4260'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4:30P Day 25 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4260' 8 5/8 csg set at 250' cwc 200 sk.

5 1/2 csg set at 4259' cw 175 sk cmt.

5 1/2 csg PBTB 4224' with perf. (4168-4176)

Filled 5 1/2 csg W/sd (4150-4224) Dumped 5 sk cmt W/dump bailer. (4110-4150)

Cutoff and recovered 3184' of 5 1/2 csg.

Pumped thru 8 5/8 plug container W/20 sk gel W/5 sk hulls, plug and 100 sk 50-50 poz

Cmt. W6% total gel. Max. pres. 300 lbs. SI pres 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. [Signature]
Well Plugging Supervisor

DATE 2/26/69

INV. NO. 9390-11