

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-145-01124-0000

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Boyd Well No. 4

Location NW NW NE Sec. 2 Twp. 23 Rge. (E) (W)17

County Pawnee Total Depth 4265

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2P Day 20 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 4265' 8 5/8 csg set at 256' cwc 200 sk.

5 1/2 csg set at 4265' cw 175 sk cmt.

5 1/2 csg PBTB 4231' and perf. (4166-4174)

Filled 5 1/2 csg W/sd (4150-4231) Dumped 5 sk cmt W/dump bailer. (4110-4250)

Cutoff and recovered 3012' of 5 1/2 csg.

Pumped thru 8 5/8 plug container 20 sk gel W/5 sk hulls, plug and 100 sk 50-50 poz cmt

W/6% total gel. Max pres 150 lbs. SI pres 0

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massing
Well Plugging Supervisor

DATE 3-21-69

INV. NO. 9493-W