

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 21 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
3-21-69

Operator's Full Name Colorado Oil Company 15-145-01122-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Boyd Well No. 2

Location SW SW NW Sec. 2 Twp. 23 Rge. 17 (E) (W) X

County Pawnee Total Depth 4270'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10A Day 20 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 4270' 8 5/8 csg set at 242' cwc 175 sk.

5 1/2 csg set at 4269' cw 175 sk cmt.

5 1/2 csg PBTD 4236 Perf. (4170-78)

Filled 5 1/2 csg W/sd (4160-4236) Dumped 5 sk cmt W/dump bailer. (4120-60)

Cutoff and recovered 2195' of 5 1/2 csg.

Pumped thru 8 5/8 plug container 20 sk gel W/5 sk hulls, plug and 100 sk 50-50 poz cmt  
with 6% total gel. Max pres 300 lbs. SI pres 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rio F. Massey  
Well Plugging Supervisor

DATE 3-21-69

INV. NO. 9495-W