

f

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 009-03364-00-00 (of this well)

Operator's Full Name National Cooperative Refinery Assn.
Complete Address Box 6 Great Bend, Kansas 67530
Lease Name Paul Dolechek Well No. 11
Location SE SE SE Sec. 24 Twp. 16 Rge. 12 (EX) (W) X
County Barton Total Depth 3373
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Kansas 67524 License No. 683
Operation Completed: Hour 3:00 PM Day 25 Month 8 Year 1977

The above well was plugged as follows:

Sanded back to 3330' and 5' sx cement with dump bailer
Ran 800' of 2" tubing in hole and pumped in 3 sx hulls.
Layed down 1 jt. of tubing and pumped in 25 sx cement.
Layed down 1 jt. of tubing and pumped in 25 sx mud gel.
Layed down Tubing to 300' and Circ. cement with 300 sx
cement to bottom of celler

Recovered 3005' of 5 1/2" casing & 75' of 10 3/4" surface casing.
3353' of 5 1/2" casing Cemented with 35 sx cement.
772' of 10 3/4" surface casing no cement. 1977 8-29-77

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Signed: Edward Rankin
Well Plugging Supervisor

INVOICED

DATE 8-31-77
INV. NO. 5741-W