

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 131-20LOCATION SE-SW-SESEC. 24 TWP. 16 RGE. 12

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 8 Lease DolecheckOperator N.C.R.A. Address 305 Kula Bldg. Wichita, K.Field _____ County BartonTotal Depth 3361 Feet.Plugging Contractor West Supply Co., Inc.Plugging Contractor's License No. 14Address Chase, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" O 275' C.W.C. 5 1/2" set 3338'
 w/ 100 sq cem. P.B. to 3120 Top perf. 3088'
 Sanded hole to 3075' dumped 5 sq cem.
 Shut off and pulled 5 1/2" casing.
 Filled hole with mud to 275' dumped
 20 sq cem over 10' rock bridge. Mud to
 35' rock bridge and 10 sq cem. to
 base of cellar

RECEIVED
 STATE CORPORATION COMMISSION

Warren H. Horner
 District Conservation Agent

Date July 15, 1955

CONSERVATION DIVISION
 WICHITA, KANSAS

7-18-55

