

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

NOV 23 1976

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -145 - 20251 - 000 (Wichita of this well)

Operator's Full Name Midwestern Supply Co., Inc.

Complete Address 207 Brown Bldg., Wichita, Kansas 67202

Lease Name White Well No. 1

Location C E/2 E/2 NW Sec. 1 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4159'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling Co.

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 ~~10~~ Day 18 Month 11 Year 1976

The above well was plugged as follows:

Total Depth 4159' 8 5/8 csg Unknown

4 1/2 csg set 4159' cw 125 sx cem.

4 1/2 csg PBSD 4150' with PFS (4114-4122)

Filled 4 1/2 csg W/sd (4150-4100) Dumped 3 sk cem W/dump bailer. (4100-4070)

Cutoff & recovered 2300' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs

hulls, released 8 5/8 plug & 125 sx Comm Cem 4% gel & shutin. FPP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bob Massey  
Well Plugging Supervisor

DATE 11-30-76

INV. NO. 4223-W