

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Thos. H. Allen

Complete Address: 925 Union Center, Wichita, Kas.

Lease Name Brothers Well No. A-3

Location NW NE NW Sec. 1 Twp. 21 Rge. 7 (X) (W)

County Rice Total Depth 3478

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364 Great Bend, Kas. License No. 399

Operation Completed: Hour 7 Pm Day 20 Month 8 Year 1962

The Above well was plugged as follows:

Filled hole with sand from TD. 3478' back to
3440'. Ran 5 say cement with dump bailer. Shot off
and pulled 5 1/2' casing. Filled hole with mud from 3405'
back to 285'. Ran 20 say cement. Filled hole with
mud from 165' back to 35'. Set a 5' rock bridge
at 30'. Ran 8 say cement from 25' back to zero.
Three' below ground level. 8 5/8" surface pipe 3' below
ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/28/62

INV. NO. 5599-W

Signed: Cecil Myerson
Well Plugging Supervisor