

To: 1 041147 15-145-20454-00-00 API NUMBER 15- Docket #D-19,030

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. SW SW NE, SEC. 20, T 23 S, R 15 W/E
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3959
Operator: Siroky Oil Management
Name & Address: P.O. Box 464, Pratt, KS 67124
Lease Name: Hall Well # 1
County: Pawnee
Well Total Depth: 4224 137.28 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well O&A _____
Other well as hereinafter indicated _____

Plugging Contractor: D S & W Well Servicing, Inc. License Number: 6901
Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:30 a.m. Day: 9 Month: 2 Year: 19 96

Plugging proposal received from: Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 4159' w/150 sx cement, PBSD 4224', Open hole 4159-4224'
1st plug sand back to 4100' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by: Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 9 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2027' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and my employees) observe this plugging.

DATE: 2-29-96
WV. NO. 44911

Signed: *Stephane Puffer*
(TECHNICIAN)

*Rec'd
2-9-96*