

3-7

To: 1 040230
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,594-00-01
NE NE NE, SEC. 10, T 28 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171
Operator: TXO Production Corporation
Name & Address 1660 Lincoln, Suite 1800
Denver, CO 80264

4950 feet from S section line
330 feet from E section line
Lease Name Kendall Well # 1
County Kiowa 154.67
Well Total Depth 4759 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well Gas Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: _____ Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4755' PBSD 3530' Perfs at 3474-3476'

1st plug sand back to 3425' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 7 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3425' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 2% gel, 2% cc by B.J. Titan. Recovered 2508' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

1) (If applicable) observe this plugging.

DATE 3-14-89

INV. NO. 24097

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
3-13-89
MAR 13 1989
CONSERVATION DIVISION
Wichita, Kansas