

1 052102

1-22

API-NUMBER 15- Drilled 1955 15.195.10573.0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

NE SW SW, SEC. 9, T 21 S, R 13 W/EX  
990 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3309

Lease Name Harter B Well # 5

Operator: Eagle Petroleum, Inc.

County Stafford 120.25

Name & Address P.O. Box 106

Well Total Depth 3700 feet

Bushton, KS 67427-0106

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 9 a.m. Day: 22 Month: 1 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 3698' w/100 sx cement, CIBP 3240', Perfs at 3385-3695', Anhydrite at 770'

1st plug run tubing to 740' and circulate cement to surface,  
2nd plug pull tubing and squeeze down 8 5/8" with 75 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:10 a.m. Day: 22 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT CIBP set at 3240'

1st plug ripped casing at 807', ran tubing to 740', circulated cement through tubing to surface with 150 sx. Pulled tubing.

2nd plug squeezed down 8 5/8" with 75 sx cement. Maximum pressure 200 psi and shut in 100 psi.

1-27-97

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 297' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

DATE JAN 28 1997

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 47463