

To: 1 052104 1-28
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-Drilled 1953 15.185.10572.0000
N/2 SE SW, SEC. 9, T 21 S, R 13 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License / 3309

990 feet from S section line
3300 feet from E section line

Operator: Eagle Petroleum
Name:
Address P.O. Box 106.
Bushton, KS 67427

Lease Name Harter B Well # 4

County Stafford 120.28

Well Total Depth 3701 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 24 Month: 1 Year: 19 97

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 3701' w/125 sx cement, Perfs at 3654-58', Casing parted at 390'-in bad shape
Believed to have CIBP at 3600', could not get down hole to find out.

1st plug run tubing to 740', pump 225 sx cement,

2nd plug run tubing to 300' and circulate cement to surface.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 28 Month: 1 Year: 1997

ACTUAL PLUGGING REPORT 1st plug ran tubing to 740' and pumped 225 sx cement. Good returns
but no cement.

2nd plug ran tubing to 300', tagged cement, pumped 60 sx cement and circulated cement to
surface.

NOTE: Lost casing ripper and jars and 50' of sinker bars in hole. 2-6-97
Also witnessed by Steve Pfeifer.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 390' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

DATE FEB 10 1997

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 47532