

8-26

To: 6 061587
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-03361-00-00
SW _____, SEC. 24, T 16 S, R 12 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5565
Operator: National Cooperative
Name & Address: Refinery Association
Box 6, Great Bend, Ks. 67530

Lease Name Dolecheck Well # 7
County Barton 108.55
Well Total Depth 3340 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00AM Day: 26 Month: Aug. Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 200 sks 60/40 Poz 6% Gel 3% Cal Cl 5 sks Hulls

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988

9-16-88

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:45AM Day: 26 Month: August Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 282' w/90 sks. 5 1/2" set at 3332' w/100 sks.

Open hole 8'. Plugged bottom w/sand and 5 sks cement to 3300'. Shot pipe
five times and recovered 1000'. Pumped in 8 5/8" 25 sks cement followed w/5
sks Hulls in 175 sks cement w/1000 Psi.

Remarks: By B. J. Titan Ran Line to 982'
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-22-88
INV. NO. 22373

Signed 
(TECHNICIAN)
Gilbert G. Scheck