

9-7

To: 6 061598
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-03378-00-00
SE 24 16 12
SEC. _____ T _____ S, R _____ W/EX
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5565
Operator: National Cooperative
Name & Address: Refinery Association
Box 6, Great Bend, Ks.
67530

Lease Name Paul Dolecheck Well # 13
County Barton 109.59
Well Total Depth 3372 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050
Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00AM Day: 7 Month: Sept Year: 19 88

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 200 sks 60/40 Poz 6% Gel 3% Cal Cl 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
CONSERVATION DIVISION
Wichita, Kansas

9-16-88

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45AM Day: 7 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 280' w/130 sks. 5 1/2" set at 3372' w/75

sks. Top perf at 3332'. Plugged bottom w/sand and 5 sks cement to 3300'. Shot pipe two times and recovered 2400'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 175 sks cement w/1100 Psi. Ran line to 1000'.

Remarks: By Halliburton
(If additional description is necessary, use BACK of this form.)

INVOLVED
DATE 9-22-88
INV. NO. 22369

Signed Gilbert G. Scheck (TECHNICIAN)
Gilbert G. Scheck