

15-185-01698.0000

4-25

15-185-01698

208

1-120416

API NUMBER 15- Drill Completion 1951

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NW, SEC. 8, T 21 S, R 13 W EX
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5163

Lease Name Reed Well # 3

Operator: Whitehawk Oil Company

County Stafford 117.81

Name & Address Box 1150

Well Total Depth 3625 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gressel Corporation License Number 5822

Address 1103 S. St. John, Lyons, KS

Company to plug at: Hour: 1 p.m. Day: 25 Month: 4 Year: 19 90

Plugging proposal received from Todd Allum

(company name) Gressel Corporation (phone) 316-257-5570

were: 5 1/2" at 3625' Perfs at 3446-3609'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 25 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3395' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 550 psi - 0 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2830' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-9-90

INV. NO. 28091

Signed Duane Rankin (TECHNICIAN)

4-25 JUN 21 1990 5-1-90