

15.185.01699.0000 4-25 15-185-01699 209

1-120415

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion 1952

NE NW NW, SEC. 8, T 21 S, R 13 W/E
4950 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5163

Lease Name Reed Well # 4
County Stafford 117.72

Operator: Whitehawk Oil Company
Name
Address Box 450 Box 3363
Great Bend, KS 67530 July 01
74101

Well Total Depth 3622 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gressel Corporation License Number 5822

Address 1103 S. St. John, Lyons, KS

Company to plug at: Hour: 3 p.m. Day: 25 Month: 4 Year: 19 90

Plugging proposal received from Todd Allum

(company name) Gressel Corporation (phone) 316-257-5570

were: 5 1/2" at 3618' PBDT 3460' Perfs at 3442-49', 3476-84', 3581-3602'

1st plug sand back to 3300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 25 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3390' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 350 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2840' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-9-90

INV. NO. 28092

Signed Duane Rankin
(TECHNICIAN)

MAY 21 1990
JUN 21 1990
4-25