

1 080349

15.185.19492.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 4-63

S/2 SE NE, SEC. 8, T 21 S, R 13 (W/E)

2970 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5310

Lease Name Fischer "A" Well # 3

Operator: Four Way Operating, Inc.

County Stafford 117.46

Name & Address Box 698

Well Total Depth 3614 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 329

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:00 pm Day: 21 Month: March Year: 19 85

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" at 3612' Perfs at 3549-57

1st plug sand back to 3500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 10 3/4" rubber plug and pump 150 sx cement.

Plugging orders given by Paul A. Luthi

Plugging Proposal Received by J. A. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45 pm Day: 21 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 10 3/4" rubber plug and pumped 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
5-25-85  
MAR 25 1985

Maximum pressure 300 psi and shut in 150 psi

Remarks: Recovered 2400' 4 1/2" casing. Used 60/40 Pozmix 4% CEMENTS 9% TAC 0% DRY SPALLIED.

INVOLVED  
3-26-85

additional description is necessary, use BACK of this form.)

DATE (did / did not) observe this plugging.

INV. NO. 7430

Signed J. A. [Signature] (TECHNICIAN) 50