

1041394

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,063.0000  
S/2 NW NW SEC. 2, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ADDRESS "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 118, 666

OPERATOR LICENSE # 5338

WELL TOTAL DEPTH 3651 FEET

OPERATOR: KAISER-FRANCIS OIL COMPANY PRODUCTION CSG: SIZE 5 1/2" @ 3650' WITH 125 SX

NAME AND PO BOX 21468 SURFACE CASING: SIZE 8 5/8" @ 378' WITH 200 SX

ADDRESS TULSA, OK 74121-1468

ABANDONED OIL WELL  GAS WELL  INPUT WELL  INJ WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 8:15 AM DAY: 14 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3276-80 & 3298-3300. CIBP @ 3552' & RETAINER @ 3505'.

SANDED BACK TO 3200' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE. PUMPED DOWN 8 5/8" SURFACE

PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER

PLUG - 125 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN PRESSURE 200#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 9:00 AM DAY: 14 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

SANDED BACK TO 3200' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE. PUMPED DOWN 8 5/8" SURFACE

PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER

PLUG - 125 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN PRESSURE 200#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2088' OF 5 1/2" CASING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

**INVOICED** SIGNED

*Stephane Pfeifer*  
(TECHNICIAN)

DATE 4/25/00

INV. NO. 06641

RECEIVED  
STATE CORPORATION COMMISSION

APR 24 2000

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3

*R*