

1 050735

API NUMBER 15- 185-22,328.0000 *R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW SE , SEC. 3 , T 21 S, R 13 *W/EX*

990 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5310  
*FOUR-WAY*  
Operator: 4-Way Operating, Inc.  
Name & Address: P. O. Box 698  
Great Bend, KS 67530

Lease Name McDonald Well # 4  
County Stafford *116.19*  
Well Total Depth 3575 Arbuckle feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A *X*

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122  
Address 704 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 pm Day: 31 Month: December Year: 19 85

Plugging proposal received from Richard Wheeler

(company name) Woodman-Iannitti (phone) 316-265-7650  
Elevation 1880'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 740'

1st plug in the Arbuckle with 30 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement.

6th plug to circulate rat hole with 15 sx cement. Plug water well from bottom to top with cement  
Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None *X*

Operations Completed: Hour: 8:45 pm Day: 31 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 744' with 50 sx cement, 2nd plug at 250' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement. Plugged water well  
with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

*INVOICED* observe this plugging.

DATE JAN 07 1986

STATE CORPORATION COMMISSION

Signed *Richard W. Lacey*  
(TECHNICIAN)

INV. NO. 11870 FEB 5 1986  
*12-31*

JAN 6 1986

1-6-86

FORM CP-2/3  
Rev. 01-84

15-185-22328-0000

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

(see rules on reverse side)

Starting Date 12 23 85  
month day year

API Number 15- 185-22,328

OPERATOR: License # 5310  
Name 4-Way Operating, Inc.  
Address P.O. Box 698  
City/State/Zip Great Bend, Kansas 67530  
Contact Person Jim Rockhold  
Phone (316) 792-2506

NW SW SE Sec 3 Twp 21 S, Rg 13 East  
990 Ft. from South Line of Section  
2310 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5122  
Name Woodman-Iannitti Drlg. Co.  
City/State Wichita, Kansas

Nearest lease or unit boundary line 330 feet  
County Stafford

Well Drilled For: Well Class: Type Equipment:  
X Oil SWD Infield X Mud Rotary  
Gas Inj X Pool Ext Air Rotary  
OWWO Expl Wildcat Cable

Lease Name McDonald Well # 4  
Ground surface elevation 1880 GL feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Surface pipe by Alternate: 1 X 2

If OWWO: old well info as follows:

Depth to bottom of fresh water 100  
Depth to bottom of usable water 200  
Surface pipe planned to be set 200  
Projected Total Depth 3600 feet  
Formation Lansing KC & Arbuckle

Operator  
Well Name  
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date 12-20-85 Signature of Operator or Agent James W. Rockhold Title President  
James W. Rockhold

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Al 1 2

This Authorization Expires 12-26-85 Approved By [Signature] 12-20-85

x 12-26-85

PUSHER Richard Wheeler  
TD 3575 FORMATION Arbuckle  
SURFACE PIPE 8 3/4 @ 218

ANHYDRITE 740 ELEVATION 1880  
STARTING TIME & DATE 7:00 pm  
COMPLETION TIME & DATE 8:45 pm 12/23/85

1st PLUG @ 744 FT. W/ 50 SX  
2nd PLUG @ 250 FT. W/ 50 SX  
3rd PLUG @ 40 FT. W/ SB40 SX  
4th PLUG @ FT. W/ SX

RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ SX  
WATER WELL PLUGGED W/ 10 SX

CEMENT COMPANY Halliborton  
TECHNICIAN Richard W. Lacey

1st Arbuckle w/ 30 SX  
2nd Base Anhydrite/SB SX  
3rd 30' oolite/SB SX  
4th 40' - 0 Rat  
15 SX

JAN 5 1986