

1 080492

API NUMBER 15- 083-21,247-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NE NE SW, SEC. 1, T 21 S, R 23 W/X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Waterhouse Well # 1

Operator: Falcon Exploration, Inc.

County Hodgeman 147.88

Name & Address Kansas State Bank Building, #1531

Well Total Depth 4550 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 557

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor R & C Drilling Company License Number 9087

Address P. O. Box 296, Hays, KS 67601

Company to plug at: Hour: 9:30 am Day: 7 Month: March Year: 19 86

Plugging proposal received from John Wise

(company name) R & C Drilling (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1484'

1st plug at: the base of the Anhydrite with 50 sx cement

2nd plug at 680' with 60 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:00 pm Day: 7 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1520' with 50 sx cement, 2nd plug at 590' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 15 sx cmeent.

Remarks: Used 60/40 Pozmix % gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

MAR 20 1986

Signed J. H. Metz (TECHNICIAN)

INV. NO. 13021 APR 10 1986

CONSERVATION DIVISION
Wichita, Kansas

3-20-86

FORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Colo
2-26-86

Starting Date February 27 1986
month day year

API Number 15- 083-21247

OPERATOR: License # 5316
Name FALCON EXPLORATION INC.
Address Suite 1531 KSB Bldg.
City/State/Zip Wichita, Kansas 67202
Contact Person Mike Mitchell
Phone (316) 262-1378

C. NE. NE SW Sec. 1 Twp. 21 S, Rg. 23
2310 Ft. from South Line of Section
2970 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9087
Name R & C Drilling Company
City/State Hays, Kansas 67601

Nearest lease or unit boundary line 330 feet
County Hodgeman
Lease Name Waterhouse Well # 1
Ground surface elevation 2289 feet MSL
Domestic well within 330 feet: —yes Xno
Municipal well within one mile: —yes Xno
Surface pipe by Alternate: 1 X 2 0
Depth to bottom of fresh water 100'
Depth to bottom of usable water 525'
* Surface pipe planned to be set 550'
Projected Total Depth 4500 feet
Formation Mississippi

Well Drilled For: Well Class: Type Equipment:
X Oil — SWD — Infield X Mud Rotary
X Gas — Inj X Pool Ext — Air Rotary
— OWWO — Expl — Wildcat — Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
— cementing will be done immediately upon setting production casing.
Date 2-26-86 Signature of Operator or Agent Craig Smith Title Geologist

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 525 feet per Alt. 1
This Authorization Expires 8-26-86 Approved By 2-26-86

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>Base Anhydrite</u> <u>1540'</u>	feet depth with	<u>50</u>	sxs of	<u>Recommend 60/40; poz. 5% gel</u>
2nd plug @ <u>680</u>	feet depth with	<u>60</u>	sxs of	
3rd plug @ <u>40</u>	feet depth with	<u>10</u>	sxs of	
4th plug @	feet depth with		sxs of	
5th plug @	feet depth with		sxs of	
(2) Rathole with <u>15</u>	sxs		(b) Mousehole with	<u>10</u>

PUSHER John W. S. E

TD 4550 FORMATION MISS

SURFACE PIPE @ 578 @ 557

ANHYDRITE 1484 - 1523 ELEVATION 2289

STARTING TIME & DATE 9:30 AM

COMPLETION TIME & DATE 3-7-86 12:00 PM

1st PLUG @ 1520 FT. W/ 50 SX

2nd PLUG @ 590 FT. W/ 50 SX

3rd PLUG @ 40 FT. W/ 58 SX

4th PLUG @ FT. W/ SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ SX

CEMENT COMPANY Hall

TECHNICIAN 6946

MAR 20 1986
CONSERVATION DIVISION
Wichita, Kansas