

1080230

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,167-0000

TECHNICIAN'S PLUGGING REPORT

N/2 NE SE, SEC. 27, T 21 S, R 21 W/X
2310 feet from N SE Corner of
660 feet from W SE Corner of
section line

Operator License # 5783

Lease Name Leadley Well # 2

Operator: Galloway Drilling Co., Inc.
Name &
Address 340 Broadway Plaza
105 S. Broadway
Wichita, KS 67202

County Hodgeman
Well Total Depth 4384 142.48 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1276

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Galloway Drilling Co., Inc. License Number 5783

Address 340 Broadway Plaza, 105 S. Broadway, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 5 Month: October Year: 19 84

Plugging proposal received from Earl McGuire

(company name) Galloway (phone) 316-263-1793

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1300' with 50 sx cement

2nd plug at 700' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:00 am Day: 5 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1300' with 50 sx cement, 2nd plug at 700' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.) 10-12-84

I (did not) observe this plugging.

Signed J. H. Metz
(TECHNICIAN)

INVOICED

DATE 10-15-84

INV. NO. 4307 / 10-5