

1 070840

8-27 15.083.20722.0000

Docket #D-20,004

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
260 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SW NE SW, SEC. 22, T 21 S, R 21 W/E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Sieverling Well # 3

Operator: Mack Energy Company

County Hodgeman

Name & Address P.O. Box 400

Well Total Depth 4402 feet

Duncan, OK 73534

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1285

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc.

License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 27 Month: 8 Year: 19 90

Plugging proposal received from Chance Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4402' w/150 sx cement, PBTD 4345' Perfs at 4328-66'

1st plug sand back to 4260' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and

150 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1870' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (15/10/1993) observe this plugging.

DATE: 8-30-90

Signed Dan Jordan (TECHNICIAN)

INV. NO. 29176

8-27