

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-22632-0000

$u\frac{1}{2}-u\frac{1}{2}$ SW, Sec. 26, T 16 S, R 12 W/X

feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

feet from W/E section line

Operator License # _____

Lease Name BOOR Well # 1

Operator: KANSAS HORIZON OIL INC
Name &

County BARTON

Address BOX 715
LYONS, KANS.
67554

Well Total Depth 3414 feet

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 " feet 615

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor NICHOLAS CASING PULLING License Number 6698

Address BOX 373 GENESEO, KANS. 67444

Company to plug at: Hour: 10:00 AM Day: 20th Month: OCT. Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO GEORGE NICHOLAS

(company name) NICHOLAS CASING PULLING (phone) 316-824-6483

were: 8 5/8" SET @ 615 FT $\frac{1}{4}$ 300 CMT. $\rightarrow$ 5 1/2" SET @ 3414 FT $\frac{1}{4}$?

PERFS-3382 FT-88 FT $\rightarrow$ SHOT 5 1/2" CSG (1) RECOVERED 2466 FT

ORDER 165 $\frac{1}{4}$ 50 FORMIX 4% GEL-3% CA-CL $\rightarrow$ 15 $\frac{1}{4}$ GEL. $\rightarrow$ 5 $\frac{1}{4}$ HULL'S

AND 8 5/8" PLUG. $\rightarrow$ PUMP IN 8 5/8" WITH PUMP TRUCK, $\rightarrow$ 25 $\frac{1}{4}$ CMT.

12 $\frac{1}{4}$ GEL. $\frac{1}{4}$ 4 $\frac{1}{4}$ HULL'S. $\rightarrow$ TO CMT. $\rightarrow$ 3 $\frac{1}{4}$ GEL. $\rightarrow$ 1 $\frac{1}{4}$ HULL'S. $\rightarrow$ RELEASE PLUG.

AND 70 $\frac{1}{4}$ CMT.

Signed M. J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:00 PM Day: 20th Month: OCT Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" SET @ 615 FT $\frac{1}{4}$ 300 CMT. $\rightarrow$ 5 1/2" SET @ 3414 FT

ORDERED 165 $\frac{1}{4}$ 50 FORMIX 4% GEL. $\rightarrow$ 3% CA-CL. $\rightarrow$ 15 $\frac{1}{4}$ GEL.

5 $\frac{1}{4}$ HULL'S AND 8 5/8" PLUG. $\rightarrow$ PUMPED IN 8 5/8" S.B. WITH PUMP TRUCK,

25 $\frac{1}{4}$ CMT. $\rightarrow$ 12 $\frac{1}{4}$ GEL. $\frac{1}{4}$ 4 $\frac{1}{4}$ HULL'S. $\rightarrow$ 70 $\frac{1}{4}$ CMT. $\rightarrow$ 3 $\frac{1}{4}$ GEL.

1 $\frac{1}{4}$ HULL'S. $\rightarrow$ RELEASED PLUG. AND 70 $\frac{1}{4}$ CMT. $\rightarrow$ MAX. PRESSURE

150 PSI @ 2 1/2 BBL'S PER MIN. (CEMENTED BY DOWELL.)

Remarks: AT BOTTOM-WITH BAILER 5 $\frac{1}{4}$ CMT. SAND TO 3330 FT
AND 5 $\frac{1}{4}$ CMT. TO COVER PERFS.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1982

I hereby certify that the above plugging instructions were given as herein stated
and that I (did) / did not) observe this plugging.

INVOICED

DATE 11-5-82

INV. NO. 1490-N

Signed M. J. Schmidt
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82