

4-060496

1-17

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-23,156 - 0000

SE NE SW /4 SEC. 26, 16 S, 12 W
990 feet from S section line
2970 feet from E section line

Operator license# 5430

Lease Dolechek well # 2

Operator: Energy Three, Inc.

County Barton

Address: P.O. Box 1505
Great Bend, Kansas 67530

Well total depth 3430 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 346 feet

111.48

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 2:00 P.M. Day: 17 Month: January Year: 94

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 180 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1994

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 2:45 P.M., Day: 17, Month: January, Year: 94

Actual plugging report: 8 5/8" to 246'. 4 1/2" to 3429' w/200 sxs.
Shot casing at 1685' and pulled to 1650'. Mixed and pumped 75 sxs. cement
with 100# hulls. Pulled casing to 840' and pumped 40 sxs. cement with
100# hulls. Pulled casing to 400' and circulated cement to surface with
65 sxs. cement. Pulled casing with cement in cellar.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: 1918 GL

I did not [X] observe the plugging.

INVOICED

[Signature]

DH (agent)

DATE FEB 02 1994

Form CP-2/3

INV. NO. 39846