

4-060495

1-17

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-23,207-00-00

N2 NE SW /4 SEC. 26, 16 S, 12 W
2310 feet from S section line
3300 feet from E section line

Operator license# 5430 Lease Dolechek well # 3

Operator: Energy Three, Inc. County Barton

Address: P.O. Box 1505 Well total depth 3440 feet
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 329 feet

111.80

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 3:00P.M. Day: 17 Month: January Year: 94

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.
Squeeze at 1500' with total 440 sxs.
Holes from 1230' - 1500' with 3 squeeze jobs.

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1994

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

CONSERVATION DIVISION
Wichita, Kansas
Years 94

Completed: Hour: 4:00P.M., Day: 17, Month: January

Actual plugging report: 8 5/8" to 329'. 4 1/2" to 3439' w/200 sxs.
Squeezed from 1230' - 1500' with 440 sxs. cement. Tied onto casing
and pumped 50 sxs. cement with 200# hulls followed by 150 sxs. cement.
Max. 1300#. S.I.P. 400#. Tied onto annulus and pumped 50 sxs. cement.
Max. 500#. S.I.P. 300#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1911 GL

I did[] did not[X] observe the plugging.

[Signature]
DA (agent)

INVOICED

DATE FEB 02 1994

INV. NO. 39847